

കേരളം കേരल KERALA

A 705007

AGREEMENT NO.....287...../KIIDC/2021-22 DATED...28.10.2021

CONTRACT AGREEMENT entered into on this 28th day of October Two Thousand Twenty One between Sri. Biju M., Venunadam, Muzhakunnu, Kannur – 670 703, Kerala. (hereinafter called the Contractor) on the one part and the Chief Engineer , M/s Kerala Irrigation Infrastructure Development Corporation Ltd., PARVATHY, TC 36/1,NH66 Service Road, Enjakkai Jn., Chakai P.O, Thiruvananthapuram – 695 024. for and on behalf of the Company (hereinafter called the Company) on the other part for the work for and on behalf of the Company (hereinafter called the Company) on the other part for the work “KIIFB PROJECT – THALASSERY HERITAGE PROJECT – PHASE 2 – Pazhassi Circuit – Puralimala Temple at Maloor in Kannur District ” by the former as per accompanying agreement, accepted tender with conditions of contract, plans, accepted schedule with specifications approved by Chief Engineer, M/s Kerala Irrigation Infrastructure Development

Accepted.


Chief Engineer
Kerala Irrigation Infrastructure
Development Corporation Ltd.
Thiruvananthapuram

7/1/21
m

2021 . 25.10.21 ,

VEDA
ENGINEERING CONSTRUCTIONS
MUZHAKKUNNU. P.O
KANNUR - 670673

Handwritten signatures and dates at the bottom left of the page.



കേരളം കേരल KERALA

W 873824

Corporation Ltd., PARVATHY, T.C. 84/3 (Old 36/1), NH66 Service Road, Enjakkal Jn., Chakai P.O., Thiruvananthapuram – 695 024., which form part of this agreement.

Signed and delivered by the above mentioned Sri. Biju M., Venunadam, Muzhakunnu, Kannur – 670 703, Kerala.

Keenaneth

Chief Engineer
Kerala Irrigation Infrastructure
Development Corporation Ltd.
Thiruvananthapuram - 695024

In the presence of:-


1. *Kumar S. Kumar*

2. *Krishnan Kulliy*

25/10 2021.

7/7
VEDA
ENGINEERING CONSTRUCTIONS
MUZHAKKUNNU, P.O
KANNUR - 670673

25/10 2021
[Handwritten signatures and text in Malayalam]



കേരളം കേരल KERALA

H 836926

Signed and delivered by Chief Engineer, Kerala Irrigation Infrastructure Development Corporation Limited, PARVATHY, T.C. 84/3 (Old 36/1), NH66 Service Road, Enjakkal Jn., Chakai P O, Thiruvananthapuram – 695024, for and on behalf of the Company.

Parvathy

Chief Engineer,
Kerala Irrigation Infrastructure Development Corporation Limited
(for and on behalf of the Company)

Chief Engineer
Kerala Irrigation Infrastructure Development Corporation Limited,
Thiruvananthapuram - 695024

In the presence of:-

1. *Kumar's Kumari*

2. *Krishnakuliy*

20206

25.10.2011

Parvathy
Kumar's Kumari
Krishnakuliy

Parvathy
VEDA
ENGINEERING CONSTRUCTIONS
MUZHAKKUNNJ. P.O
KANNUK - 670573

MEMORANDUM OF WORK TEDERED

Name of work	“KIIFB PROJECT – THALASSERY HERITAGE PROJECT – PHASE 2 – Pazhassi Circuit – Puralimala Temple at Maloor in Kannur District ”
Estimate P.A.C	Rs. 57,68,493/-
Contract P.A.C	Rs. 62,79,215.13/-
Date of starting	The work should be started within 10 days after executing agreement
Date of completion	12 months from the date of handing over the site
Performance Guarantee	Treasury FD for an amount of Rs. 1,34,000/- JL 1616838 dated 26.10..2021 for 7 years. Treasury FD for an amount of Rs. 55,500/- JL 1616837 dated 26.10..2021 for 3 years.

Accepted.

Chief Engineer
Kerala Irrigation Infrastructure
Development Corporation Ltd.
Thiruvananthapuram - 695024

7/11

VEDA
ENGINEERING CONSTRUCTIONS
MUZHAKKUNNU. P.O
KANNUR - 670673

Signature

Chief Engineer
Kerala Irrigation Infrastructure
Development Corporation Ltd.
Thiruvananthapuram - 695024

7145

VEDA
ENGINEERING CONSTRUCTIONS
MUZHAKKUNNU. P.O
Kerala - 695000

FORM OF NOMINATION

I, Sri. Biju M., Venunadam, Muzhakunnu, Kannur – 670 703, Kerala. do hereby nominate and authorize
..... to receive all or any sum found due to me under the terms of contract (Agreement No...../KIIDC/ 2021-22 dated) and details of contract in the event of my death before the amount has become payable or having become but has become payable or having become payable but has not been paid.

Signature

[Handwritten Signature]

Name:

Biju M

Address:

Venunadam, Muzhakunnu

VEDA
ENGINEERING CONSTRUCTION
MUZHAKKUNNU. P.O
KANNUR - 670673

In the presence of witness:

1.

2.

[Handwritten Signature] - Chief Engineer
Kerala Irrigation Infrastructure
Development Corporation Ltd.
Thiruvananthapuram - 695024
Chief Engineer,
KIIDC Limited
Thiruvananthapuram

Item Rate Boq

Tender Inviting Authority: KERALA IRRIGATION INFRASTRUCTURE DEVELOPMENT CORPORATION LIMITED

Work Name : KILFB PROJECT - THALASSERY HERITAGE PROJECT - PHASE 2 - Pazhassi Circuit - Puralimala Temple at Malloor in Kannur District


Contract No: KIIDC/Retender/402-1/2021-22


Bidder Name: BIJU M

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

PRICE SCHEDULE

NUMBER	TEXT #	NUMBER #	TEXT #	NUMBER	NUMBER #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	Estimated Rate	BASIC RATE In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT Without Taxes	TOTAL AMOUNT In Words	TEXT #
1	1	4	5	6	13	53		55
1.01	NADAPPANTHAL 2.6.1 : Earth work in excavation by mechanical means (hydraulic excavator)/manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including disposal of excavated earth, lead up to 50 m and lift up to 1.5 m, disposed earth to be levelled and neatly dressed. All kinds of soil	24.3600	cum		177.0	4311.72	INR Four Thousand Three Hundred & Eleven and Paise Seventy Two Only	
1.02	2.3.1 : Clearing jungle including uprooting of rank vegetation, grass, brush wood, trees and saplings of girth up to 30 cm measured at a height of 1 m above ground level and removal of rubbish up to a distance of 50 m outside the periphery of the area cleared	4000.0000	sqm		9.5	38000.00	INR Thirty Eight Thousand Only	
1.03	4.1.6 : Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level: 1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 40 mm nominal size)	10.6810	cum		6750.0	72096.75	INR Seventy Two Thousand & Ninety Six and Paise Seventy Five Only	


VEDA
ENGINEERING CONSTRUCTIONS
MUZHAKKUNNU PO
KANNUR - 670673


Kerala Irrigation Infrastructure
Development Corporation Ltd.
Thiruvananthapuram - 695024

1.04	7.1.1 : Random rubble masonry with hard stone in foundation and plinth including levelling up with cement concrete 1:6:12 (1 cement : 6 coarse sand : 12 graded stone aggregate 20 mm nominal size) up to plinth level with Cement mortar 1:6 (1 cement : 6 coarse sand)	16.7040	cum	5600.0	93542.40	INR Ninety Three Thousand Five Hundred & Forty Two and Paise Forty Only
1.05	od215233/2019_2020 : Special Type red colour exposed latente stone masonry work for superstructure wall including all cost labour charges etc.Complete	10.4400	cum	16610.0	173304.00	INR One Lakh Seventy Three Thousand Three Hundred & Four Only
1.06	5.9.5 : Centering and shuttering including strutting, etc. and removal of form for:Lintels, beams, plinth beams, girders bressumers and cantilevers	6.9600	sqm	435.0	3375.60	INR Three Thousand Three Hundred & Seventy Five and Paise Sixty Only
1.07	5.1.2 : Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level: 1:1.5:3 (1 cement 1.5 coarse sand :3 graded stone aggregate 20 mm nominal size	2.0880	cum	8780.0	18332.64	INR Eighteen Thousand Three Hundred & Thirty Two and Paise Sixty Four Only
1.08	11.26.1 : Kota stone slab flooring over 20 mm (average) thick base laid over and jointed with grey cement slurry mixed with pigment to match the shade of the slab, including rubbing and polishing complete with base of cement mortar 1:4 (1 cement : 4 coarse sand)25 mm thick	72.0000	sqm	1630.0	117360.00	INR One Lakh Seventeen Thousand Three Hundred & Sixty Only
1.09	13.48.1 : Finishing with Deluxe Multi surface paint system for interiors and exteros using primer as per manufacturers specifications: Two or more coats applied on walls @ 1.25 ltr/10 sqm over and including one coat of special primer applied @ 0.75 ltr /10 sqm	8.6400	sqm	140.0	1209.60	INR One Thousand Two Hundred & Nine and Paise Sixty Only
1.1	5.22.6 : Steel reinforcement for R.C.C work including straightening, cutting, bending, placing in position and binding all complete upto plinth levelThermo - Mechanically Treated bars of grade Fe-500D or more	278.5000	kilogram	80.0	22280.00	INR Twenty Two Thousand Two Hundred & Eighty Only
1.11	2.25 : Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20 cm in depth, consolidating each deposited layer by ramming and watering. lead up to 50 m and lift up to 1.5 m.	31.6250	cum	177.0	5597.63	INR Five Thousand Five Hundred & Ninety Seven and Paise Sixty Two Only

VEDA
ENGINEERING CONSTRUCTIONS
CHENNAI

Reviewed
Development Corporation Ltd.
Thiruvananthapuram - 695024

1.12	50.67.1 : Laterate masonry with neatly dressed laterate stone of size 40x20x15cm or nearest size in cement mortar 1:6 for foundation and basement including all cost of materials, labour charges etc.	0.7020	cum					6670.0	4682.34	INR Four Thousand Six Hundred & Eighty Two and Paise Thirty Four Only
1.13	od105144/2020_2021 : Applying 2 coats of Weather Shield clear coat of approved brand (DULUX or Equivalent) over wall surface thoroughly cleaned for removing dust and debris accumulated after construction and Pointing. Pointing to be with Cement Mortar 1:3 (1 cement & 3 Fine Sand). Wall surface need to be cleared of cracks and holes above 2cm in dia using crack filler of approved brand (AREDX ENDURA or Equivalent) with colour matching that of laterite.	9.3600	sqm					690.0	5616.00	INR Five Thousand Six Hundred & Sixteen Only
1.14	od212714/2019_2020 : Providing granite stone pillars of size 30cm and height 2.70m with ornamental carvings and decorative base and collars as per the drawing of the Architect including all cost and conveyance, labour charges etc complete as per the direction of Engineer at site	12.0000	each					45500.0	546000.00	INR Five Lakh Forty Six Thousand Only
1.15	10.16.2 : Steel work in built up tubular (round, square or rectangular hollow tubes etc.) trusses etc., including cutting, hoisting, fixing position and applying a priming coat of approved steel primer, including welding and bolted with special shaped washers etc. complete. Hot finished seamless type tubes	3150.0000	kg					130.0	409500.00	INR Four Lakh Nine Thousand Five Hundred Only
1.16	od215231/2019_2020 : Providing & fixing on roof pressed clay ceiling tiles 30x25mm size of 20 mm nominal thickness and of approved size and as per approved pattern on steel frame work complete (steel frame work to be paid separately).	126.0000	sqm					335.0	42210.00	INR Forty Two Thousand Two Hundred & Ten Only
1.17	12.48 : Providing & fixing on roof pressed clay tile (Mangalore tile) of 20 mm nominal thickness and of approved size and as per approved pattern on steel frame work complete (steel frame work to be paid separately)	126.0000	sqm					336.0	42336.00	INR Forty Two Thousand Three Hundred & Thirty Six Only
1.18	12.49 : Providing & laying on roof pressed clay tile ridge (Mangalore tile) of 20 mm thickness and of approved pattern on steel frame work complete (steel frame work to be paid separately).	25.8000	metre					74.0	1909.20	INR One Thousand Nine Hundred & Nine and Paise Twenty Only

1.19	od215232/2019_2020 : Providing and fixing teakwood eve board 20cm wide including all charges etc, complete	43.5000	per metre						3000.0	130500.00	INR One Lakh Thirty Thousand Five Hundred Only
2	WAITING SHED										
2.01	2.6.1 : Earth work in excavation by mechanical means (Hydraulic excavator/manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including disposal of excavated earth, lead up to 50 m and lift up to 1.5 m, disposed earth to be levelled and neatly dressed.All kinds of soil	12.8300	cum						178.0	2283.74	INR Two Thousand Two Hundred & Eighty Three and Paise Seventy Four Only
2.02	4.1.6 : Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level:1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 40 mm nominal size)	1.0100	cum						6800.0	6868.00	INR Six Thousand Eight Hundred & Sixty Eight Only
2.03	7.1.1 : Random rubble masonry with hard stone in foundation and plinth including levelling up with cement concrete 1:6:12 (1 cement : 6 coarse sand : 12 graded stone aggregate 20 mm nominal size) up to plinth level with Cement mortar 1:6 (1 cement : 6 coarse sand)	4.8480	cum						5600.0	27148.80	INR Twenty Seven Thousand One Hundred & Forty Eight and Paise Eighty Only
2.04	5.9.5 : Centering and shuttering including strutting, etc. and removal of form for:Lintels, beams, plinth beams, girders bressumers and cantilevers	2.0200	sqm						485.0	979.70	INR Nine Hundred & Seventy Nine and Paise Seventy Only
2.05	5.1.2 : Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level:1:1:5:3 (1 cement 1.5 coarse sand :3 graded stone aggregate 20 mm nominal size	4.2240	cum						8780.0	37086.72	INR Thirty Seven Thousand & Eighty Six and Paise Seventy Two Only
2.06	2.25 : Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20 cm in depth, consolidating each deposited layer by ramming and watering, lead up to 50 m and lift up to 1.5 m.	3.1000	cum						177.0	548.70	INR Five Hundred & Forty Eight and Paise Seventy Only
2.07	50.6.7.1 : Laterite masonry with neatly dressed laterite stone of size 40x20x15cm or nearest size in cement mortar 1:6 for foundation and basement including all cost of materials, labour charges etc.	2.7270	cum						6670.0	18189.09	INR Eighteen Thousand One Hundred & Eighty Nine and Paise Nine Only

VEDA
ENGINEERING CONSTRUCTIONS
MUZHAKUNNU, P.O.
670673

Release
Kerala Infrastructure
Development Corporation Ltd.
Thiruvananthapuram - 695024

2.08	od105144/2020_2021 : Applying 2 coats of Weather Shield clear coat of approved brand (DULUX or Equivalent) over wall surface thoroughly cleaned for removing dust and debris accumulated after construction and Pointing. Pointing to be with Cement Mortar 1:3 (1 cement & 3 Fine Sand). Wall surface need to be cleared of cracks and holes above 2cm in dia using crack filler of approved brand (AREDX ENDURA or Equivalent) with colour matching that of laterite.	6.0600	sqm	600.0	3636.00	INR Three Thousand Six Hundred & Thirty Five and Paise One Hundred Only
2.09	5.22.6 : Steel reinforcement for R.C.C work including straightening, cutting, bending, placing in position and binding all complete upto plinth levelThermo - Mechanically Treated bars of grade Fe-500D or more	141.4000	kilogram	80.0	11312.00	INR Eleven Thousand Three Hundred & Twelve Only
2.1	4.1.8 : Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level:1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40 nominal size)	0.9300	cum	6325.0	5882.25	INR Five Thousand Eight Hundred & Eighty Two and Paise Twenty Five Only
2.11	11.46.1 : Providing and laying Vitrified tiles indifferent sizes (thickness to be specified by manufacturer), with water absorption less than 0.08 % and conforming to I.S. 15622, of approved make, in all colours & shade, in skirting, riser of steps, over 12 mm thick bed of cement mortar 1:3 (1 cement : 3 coarse sand), including grouting the joint with white cement & matching pigments etc. complete. Size of Tile 500x500 mm	6.2000	sqm	1420.0	8804.00	INR Eight Thousand Eight Hundred & Four Only
2.12	5.2.2 : Reinforced cement concrete work in walls (any thickness), including attached plasters, buttresses, plinth and string courses, fillats, columns, pillars, piers, abutments, posts and struts etc. up to floor five level excluding cost of centering, shuttering, finishing and reinforcement : 1:1.5:3 (1 cement : 1.5 coarse sand : 3 graded stone aggregate 20 mm nominal size)	0.5660	cum	10100.0	5716.60	INR Five Thousand Seven Hundred & Sixteen and Paise Sixty Only
2.13	5.9.6 : Centering and shuttering including strutting, etc. and removal of form for Columns, Pillars, Piers, Abutments, Posts and Struts	7.5360	sqm	650.0	4973.76	INR Four Thousand Nine Hundred & Seventy Three and Paise Seventy Six Only
2.14	5.22A.6 : Steel reinforcement for R.C.C work including straightening, cutting, bending, placing in position and binding all complete above plinth level Thermo - Mechanically Treated bars of grade Fe-500D or more	56.6000	kg	30.0	4528.00	INR Four Thousand Five Hundred & Twenty Eight Only

2.15	10.16.2 : Steel work in built up tubular (round, square or rectangular hollow tubes etc.) trusses etc., including cutting, hoisting, fixing position and applying a priming coat of approved steel primer, including welding and bolting with special shaped washers etc. complete. Hot finished seamless type tubes	638.0000	kg	132.0	84216.00	INR Eighty Four Thousand Two Hundred & Sixteen Only
2.16	od215232/2019_2020 : Providing and fixing teakwood eve board 20cm wide including all charges etc. complete	19.4000	per metre	3170.0	61498.00	INR Sixty One Thousand Four Hundred & Ninety Seven and Paise One Hundred Only
2.17	od215234/2019_2020 : Providing & fixing on roof pressed clay tile (Mangalore tile) of 20 mm nominal thickness and of approved size and as per approved pattern on steel frame work complete (inner side)	25.5200	sqm	760.0	19395.20	INR Nineteen Thousand Three Hundred & Ninety Five and Paise Twenty Only
2.18	12.49 : Providing & laying on roof pressed clay tile ridge (Mangalore tile) of 20 mm thickness and of approved pattern on steel frame work complete (steel frame work to be paid separately).	11.6000	metre	74.0	858.40	INR Eight Hundred & Fifty Eight and Paise Forty Only
3	OFFICE					
3.01	2.6.1 : Earth work in excavation by mechanical means (hydraulic excavator)/manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including disposal of excavated earth, lead up to 50 m and lift up to 1.5 m, disposed earth to be levelled and neatly dressed. All kinds of soil	47.7450	cum	177.0	8451.04	INR Eight Thousand Four Hundred & Fifty One and Paise Four Only
3.02	4.1.6 : Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level: 1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 40 mm nominal size)	13.3470	cum	6670.0	89024.49	INR Eighty Nine Thousand & Twenty Four and Paise Forty Nine Only
3.03	7.1.1 : Random rubble masonry with hard stone in foundation and plinth including levelling up with cement concrete 1:6:12 (1 cement : 6 coarse sand : 12 graded stone aggregate 20 mm nominal size) up to plinth level with Cement mortar 1:6 (1 cement : 6 coarse sand)	40.2850	cum	5600.0	225596.00	INR Two Lakh Twenty Five Thousand Five Hundred & Ninety Five and Paise One Hundred Only
3.04	5.9.5 : Centering and shuttering including strutting, etc. and removal of form for Lintels, beams, plinth beams, girders, bressumers and cantilevers	49.8410	sqm	434.0	24123.04	INR Twenty Four Thousand One Hundred & Twenty Three and Paise Four Only

VEDA
ENGINEERING CONSTRUCTIONS
MUTHAKUNNU, P.O
VANNUR - 670673

See next
Infrastructure
Development Corporation Ltd.
Thiruvananthapuram - 695024

3.05	5.1.2 : Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level 1:1.5:3 (1 cement 1.5 coarse sand :3 graded stone aggregate 20 mm nominal size	4.5230	cum	8780.0	39711.94	INR Thirty Nine Thousand Seven Hundred & Eleven and Paise Ninety Four Only
3.06	5.22.6 : Steel reinforcement for R.C.C work including straightening, cutting, bending, placing in position and binding all complete upto plinth levelThermo - Mechanically Treated bars of grade Fe-500D or more	452.3000	kilogram	80.0	36184.00	INR Thirty Six Thousand One Hundred & Eighty Four Only
3.07	2.25 : Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20 cm in depth, consolidating each deposited layer by ramming and watering, lead up to 50 m and lift up to 1.5 m.	31.1970	cum	175.0	5459.48	INR Five Thousand Four Hundred & Fifty Nine and Paise Forty Seven Only
3.08	11.26.1 : Kota stone slab flooring over 20 mm (average) thick base laid over and jointed with grey cement slurry mixed with pigment to match the shade of the slab, including rubbing and polishing complete with base of cement mortar 1:4 (1 cement : 4 coarse sand)25 mm thick	69.3250	sqm	1640.0	113693.00	INR One Lakh Thirteen Thousand Six Hundred & Ninety Three Only
3.09	50.6.7.2 : Laterite masonry with neatly dressed laterite stone of size 40x20x15cm or nearest size in cement mortar 1:6 for super structure above plinth level up to floor two level including all cost of materials, labour charges etc.	26.9350	cum	7200.0	193932.00	INR One Lakh Ninety Three Thousand Nine Hundred & Thirty Two Only
3.1	od105144/2020_2021 : Applying 2 coats of Weather Shield clear coat of approved brand (DULUX or Equivalent) over wall surface thoroughly cleaned for removing dust and debris accumulated after construction and Pointing. Pointing to be with Cement Mortar 1:3 (1cement & 3 Fine Sand). Wall surface need to be cleared of cracks and holes above 2cm in dia using crack filler of approved brand (AREDX ENDURA or Equivalent) with colour matching that of laterite.	269.3340	sqm	580.0	156213.72	INR One Lakh Fifty Six Thousand Two Hundred & Thirteen and Paise Seventy Two Only


VEDA
ENGINEERING CONSTRUCTIONS
 MILZHAKKUNNU, P.O
 KANNUR-670613


 Director
 Kerala Irrigation Infrastructure
 Development Corporation Ltd.
 Thiruvananthapuram - 695024

3.11	9.1.1 : Providing wood work in frames of doors, windows, clerestory windows and other frames, wrought framed and fixed in position with hold fast lugs or with dash fasteners of required dia & length (hold fast lugs or dash fastener shall be paid for separately). Second class teak wood	0.3950	cum					131030.0	51756.85	INR Fifty One Thousand Seven Hundred & Fifty Six and Paise Eighty Five Only
3.12	9.5.1.1 : Providing and fixing panelled or panelled and glazed shutters for shutters for doors, windows and clerestory windows, including ISI marked M.S. pressed butt hinges bright finished of required size with necessary screws, excluding panelling which will be paid for separately, all complete as per direction of Engineer - in-charge. Second class teak wood 35 mm thick shutters	13.5030	sqm					3600.0	48610.80	INR Forty Eight Thousand Six Hundred & Ten and Paise Eighty Only
3.13	10.16.2 : Steel work in built up tubular (round, square or rectangular hollow tubes etc.) trusses etc., including cutting, hoisting, fixing position and applying a priming coat of approved steel primer, including welding and bolted with special shaped washers etc. complete. Hot finished seamless type tubes	3694.0250	kg					130.0	480223.25	INR Four Lakh Eighty Thousand Two Hundred & Twenty Three and Paise Twenty Five Only
3.14	04215232/2019_2020 : Providing and fixing teakwood eve board 20cm wide including all charges etc. complete	46.6000	per metre					3170.0	147722.00	INR One Lakh Forty Seven Thousand Seven Hundred & Twenty Two Only
3.15	12.48 : Providing & fixing on roof pressed clay tile (Mangalore tile) of 20 mm nominal thickness and of approved size and as per approved pattern on steel frame work complete (steel frame work to be paid separately)	147.7610	sqm					340.0	50238.74	INR Fifty Thousand Two Hundred & Thirty Eight and Paise Seventy Four Only
3.16	04215252/2019_2020 : Providing & fixing on roof pressed clay ceiling tiles (30 x 25) mm size of 20 mm nominal thickness and of approved size and as per approved pattern on steel frame work complete (steel frame work to be paid separately).	147.7610	sqm					340.0	50238.74	INR Fifty Thousand Two Hundred & Thirty Eight and Paise Seventy Four Only
3.17	12.49 : Providing & laying on roof pressed clay tile ridge (Mangalore tile) of 20 mm thickness and of approved pattern on steel frame work complete (steel frame work to be paid separately).	28.6000	metre					74.0	2116.40	INR Two Thousand One Hundred & Sixteen and Paise Forty Only

Reviewed

VEDA
ENGINEERING CONSTRUCTIONS
 MUZHAKKUNNI, P.O.
 KANNUR - 690073

Kerala Irrigation Infrastructure
 Development Corporation Ltd.
 Thiruvananthapuram - 695024

3.18	od215236/2019_2020 : Providing and fixing 8" or nearest size punt antique tower bolt including all cost and labour charges	9.0000	each		520.0	4680.00	INR Four Thousand Six Hundred & Eighty Only
3.19	od215238/2019_2020 : Providing and fixing 4" SS punt hinges antique (approved by the architect)including all cost and labour charges.	38.0000	each		1070.0	40660.00	INR Forty Thousand Six Hundred & Sixty Only
3.2	od215239/2019_2020 : Providing and fixing Antique Brass handle ring including all cost and labour charges	2.0000	each		1500.0	3000.00	INR Three Thousand Only
3.21	od215240/2019_2020 : Providing and fixing of door lock: Atom sixum Lock ultra key ant.	3.0000	no		3425.0	10275.00	INR Ten Thousand Two Hundred & Seventy Five Only
3.22	13.9.2 : Cement plaster 1:3 (1 cement : 3 coarse sand) finished with a floating coat of neat cement,20 mm cement plaster	17.7760	sqm		450.0	7999.20	INR Seven Thousand Nine Hundred & Ninety Nine and Paise Twenty Only
3.23	13.6.1 : 20 mm cement plaster of mix:1:4 (1 cement : 4 coarse sand)	16.1560	sqm		430.0	6947.08	INR Six Thousand Nine Hundred & Forty Seven and Paise Eight Only
4	TOILET						
4.01	2.6.1 : Earth work in excavation by mechanical means (Hydraulic excavator/manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including disposal of excavated earth, lead up to 50 m and lift up to 1.5 m, disposed earth to be levelled and neatly dressed.All kinds of soil	6.5020	cum		178.0	1157.36	INR One Thousand One Hundred & Fifty Seven and Paise Thirty Six Only
4.02	4.1.8 : Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level:1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40 nominal size)	2.0410	cum		6330.0	12919.53	INR Twelve Thousand Nine Hundred & Nineteen and Paise Fifty Three Only
4.03	7.1.1 : Random rubble masonry with hard stone in foundation and plinth including levelling up with cement concrete 1:6:12 (1 cement : 6 coarse sand : 12 graded stone aggregate 20 mm nominal size) up to plinth level with:Cement mortar 1:6 (1 cement : 6 coarse sand)	44.5860	cum		5600.0	249681.60	INR Two Lakh Forty Nine Thousand Six Hundred & Eighty One and Paise Sixty Only

[Handwritten Signature]

VEDA

ENGINEERING CONSTRUCTIONS

MUZHAKKUNJU PO
KANNUR - 670673

[Handwritten Signature]

Kerala Infrastructure Development Corporation Ltd.
Thiruvananthapuram - 695024

4.04	qd215230/2019_2020 : Special type red colour Exposed Laterite stone masonry with neatly dressed laterite stone of size 30x20x20cm or nearest size in cement mortar 1:6 for superstructure above plinth level upto floor two level including all cost and conveyance labour charges etc. complete	1.6200	cum			16630.0	26940.60	INR Twenty Six Thousand Nine Hundred & Forty and Paise Sixty Only
4.05	5.9.5 : Centering and shuttering including strutting, etc. and removal of form for Lintels, beams, plinth beams, girders, bressumers and cantilevers	3.4620	sqm			485.0	1679.07	INR One Thousand Six Hundred & Seventy Nine and Paise Seven Only
4.06	5.1.2 : Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level 1:1.5:3 (1 cement 1.5 coarse sand : 3 graded stone aggregate 20 mm nominal size	0.9090	cum			8780.0	7981.02	INR Seven Thousand Nine Hundred & Eighty One and Paise Two Only
4.07	5.22.6 : Steel reinforcement for R.C.C work including straightening, cutting, bending, placing in position and binding all complete upto plinth level Thermo - Mechanically Treated bars of grade Fe-500D or more	94.5360	kilogram			80.0	7562.88	INR Seven Thousand Five Hundred & Sixty Two and Paise Eighty Eight Only
4.08	2.25 : Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20 cm in depth, consolidating each deposited layer by ramming and watering, lead up to 50 m and lift up to 1.5 m.	4.5370	cum			178.0	807.59	INR Eight Hundred & Seven and Paise Fifty Nine Only
4.09	50.6.1.2 : Solid block masonry using pre cast solid blocks (factory made) of size 40x20x20cm or nearest available size conforming to IS 2185 part 1 of 1979 for super structure up to floor two level thickness 20cm and above in: CM 1:6 (1 cement: 6 coarse sand) etc complete.	6.8840	cum			6200.0	42680.80	INR Forty Two Thousand Six Hundred & Eighty and Paise Eighty Only
4.1	13.1.1 : 12 mm cement plaster of mix:1:4 (1 cement : 4 fine sand)	56.3110	sqm			225.0	12669.98	INR Twelve Thousand Six Hundred & Sixty Nine and Paise Ninety Eight Only

VEDA
ENGINEERING CONSTRUCTIONS

ENGINEERING CONSTRUCTIONS
MULHAKKUNNU, P.O
KANNUR - 670673

Deevaraj
Engineer

Kerala Irrigation Infrastructure
Development Corporation Ltd.
Thiruvananthapuram - 695024

4.11	11.36 : Providing and fixing 1st quality ceramic glazed wall tiles conforming to IS : 15622 (thickness to be specified by the manufacturer), of approved make, in all colours, shades except burgundy, bottle green, black of any size as approved by Engineer-in-Charge, in skirting, risers of steps and dados, over 12 mm thick bed of cement mortar 1:3 (1 cement : 3 coarse sand) and jointing with grey cement slurry @ 3.3 kg per sqm, including pointing in white cement mixed with pigment of matching shade complete.	16,8710	sqm			1180.0	19907.78	INR Nineteen Thousand Nine Hundred & Seven and Paise Seventy Eight Only
4.12	11.37 : Providing and laying Ceramic glazed floor tiles of size 300x300 mm (thickness to be specified by the manufacturer), of 1st quality conforming to IS : 15622, of approved make, in colours such as White, Ivory, Grey, Fume Red Brown, laid on 20 mm thick cement mortar 1:4 (1 Cement : 4 Coarse sand), including pointing the joints with white cement and matching pigment etc., complete.	7.5610	sqm			1500.0	11341.50	INR Eleven Thousand Three Hundred & Forty One and Paise Fifty Only
4.13	13.48.1 : Finishing with Deluxe Multi surface paint system for interiors and exteriors using primer as per manufacturers specifications: Two or more coats applied on walls @ 1.25 lit/10 sqm over and including one coat of special primer applied @ 0.75 lit/10 sqm	34.2960	sqm			138.0	4733.26	INR Four Thousand Seven Hundred & Thirty Three and Paise Twenty Six Only
4.14	od215248/2019_2020 : Providing and fixing C.P. brass bib cock of approved quality conforming to IS:8931,18.49,1 15 mm nominal bore	2.0000	each			3210.0	6420.00	INR Six Thousand Four Hundred & Twenty Only
4.15	od215249/2019_2020 : 17.34 Providing and fixing toilet paper holder:17.34.1 C.P. brass(modified)	2.0000	each			1600.0	3200.00	INR Three Thousand Two Hundred Only
4.16	od215250/2019_2020 : Providing & fixing on roof pressed clay tile (Mangalore tile) of 20 mm nominal thickness and of approved size and as per approved pattern on steel frame work complete (steel frame work to be paid separately)	22.1400	sqm			336.0	7439.04	INR Seven Thousand Four Hundred & Thirty Nine and Paise Four Only
4.17	12.49 : Providing & laying on roof pressed clay tile ridge (Mangalore tile) of 20 mm thickness and of approved pattern on steel frame work complete (steel frame work to be paid separately).	10.8000	metre			74.0	799.20	INR Seven Hundred & Ninety Nine and Paise Twenty Only
5	PATHWAY							

See above

Chief Engineer

VEDA CONSTRUCTIONS
ENGINEERING & CONSTRUCTION
MULTI-HAKKUNNUNJI P.O.
KANNUR - 670613

Kerala Irrigation Infrastructure
Development Corporation Ltd.
Thiruvananthapuram - 695024

5.01	16.1 : Preparation and consolidation of sub grade with power road roller of 8 to 12 tonne capacity after excavating earth to an average of 22.5 cm depth, dressing to camber and consolidating with road roller including making good the undulations etc. and re-rolling the sub grade and disposal of surplus earth with lead upto 50 metres.	316.0000	sqm					128.0	40448.00	INR Forty Thousand Four Hundred & Forty Eight Only
5.02	16.78.1 : Construction of granular sub- base by Providing close graded Material conforming to specifications, mixing in a mechanical mix plant at OMC, Camage of mixed material by tipper to work site, for all leads & lifts, spreading in uniform layers of specified thickness with motor grader on prepared surface and compacting with vibratory power roller to achieve the desired density, complete as per specifications and directions of Engineer-in- Charge. With Material conforming to Grade - I (size range 75 mm to 0.075 mm) having CBR Value-30	47.4000	cum					2410.0	114234.00	INR One Lakh Fourteen Thousand Two Hundred & Thirty Four Only
5.03	ord258363/2020_2021 : Providing and laying rough finish narasapuram stone flooring in required design and pattern (55.88 cm x 55.88 cm) or (86.36 x 55.88 cm) or the nearest in linear as well as curvilinear all complete as per the architectural drawing with 40 - 50 mm thick stone slab over 50 mm thick compacted bed of 6 mm stone aggregate etc. complete as specified and as directed by the engineer in charge(including transportation and labor charges)	316.0000	sqm					1990.0	628840.00	INR Six Lakh Twenty Eight Thousand Eight Hundred & Forty Only
5.04	16.69 : Providing and laying at or near ground level factory made kerb stone of M-25 grade cement concrete in position to the required line, level and curvature jointed with cement mortar 1:3 (1 cement : 3 coarse sand) , including making joints with or without grooves (thickness of joints except at sharp curve shall not to more than 5 mm), including making drainage opening wherever required complete etc. as per direction of Engineer-in-charge (length of finished kerb edging shall be measured for payment) : (Precast C. C. kerb stone shall be approved by Engineer-in-Charge)	14.2200	cum					7085.0	100748.70	INR One Lakh Seven Hundred & Forty Eight and Paise Seventy Only



VEDA

ENGINEERING CONSTRUCTIONS

 MUTHAKKUNNU, P.O.

 KANNUR - 6700673



 CHIEF ENGINEER

 Kerala Infratech Infrastructure

 Development Corporation Ltd.

 Thiruvananthapuram - 695024

5.05	2.8.1 : Earth work in excavation by mechanical means (Hydraulic excavator) /manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift up to 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. All kinds of soil	0.5000	cum		235.0	117.50	INR One Hundred & Seventeen and Paise Fifty Only
5.06	4.1.8 : Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level 1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40 nominal size)	0.1000	cum		6325.0	632.50	INR Six Hundred & Thirty Two and Paise Fifty Only
5.07	5.1.2 : Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level 1:1:5:3 (1 cement 1.5 coarse sand : 3 graded stone aggregate 20 mm nominal size)	0.4000	cum		8780.0	3512.00	INR Three Thousand Five Hundred & Twelve Only
5.08	5.9.2 : Centering and shuttering including strutting, etc. and removal of form for Walls (any thickness) including attached pilasters, buttresses, plinth and string courses etc.	4.4000	sqm		535.0	2354.00	INR Two Thousand Three Hundred & Fifty Four Only
5.09	5.22.6 : Steel reinforcement for R.C.C work including straightening, cutting, bending, placing in position and binding all complete upto plinth level Thermo - Mechanically Treated bars of grade Fe-500D or more	40.0000	kilogram		80.0	3200.00	INR Three Thousand Two Hundred Only
6	WATER TANK						
6.01	2.6.1 : Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including disposal of excavated earth, lead up to 50 m and lift up to 1.5 m, disposed earth to be levelled and neatly dressed. All kinds of soil	2.0800	cum		177.0	368.16	INR Three Hundred & Sixty Eight and Paise Sixteen Only
6.02	4.1.8 : Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level 1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40 nominal size)	0.2570	cum		6325.0	1625.53	INR One Thousand Six Hundred & Twenty Five and Paise Fifty Three Only

VEDA
ENGINEERING CONSTRUCTIONS
MUZHAKUNNU, P.O
KANNUR - 670673

Research
Kerala Irrigation Infrastructure
Development Corporation Ltd.
Tadavangalapuram - 695024

6.03	5.1.2 : Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level: 1:1.5:3 (1 cement 1.5 coarse sand :3 graded stone aggregate 20 mm nominal size)	0.2250	cum	8790.0	1975.50	INR One Thousand Nine Hundred & Seventy Five and Paise Fifty Only
6.04	5.2.2 : Reinforced cement concrete work in walls (any thickness), including attached pilasters, buttresses, plinth and string courses, fillers, columns, pillars, piers, abutments, posts and struts etc. up to floor five level excluding cost of centering, shuttering, finishing and reinforcement : 1:1.5:3 (1 cement : 1.5 coarse sand : 3 graded stone aggregate 20 mm nominal size)	5.6820	cum	10100.0	57388.20	INR Fifty Seven Thousand Three Hundred & Eighty Eight and Paise Twenty Only
6.05	5.3 : Reinforced cement concrete work in beams, suspended floors, roofs, having slope up to 15 degrees landings, balconies, shelves, chajjas, lintels, bands, plain window sills, staircases and spiral stair cases up to floor five level excluding the cost of centering, shuttering, finishing and reinforcement, with: 1:1.5:3 (1 cement : 1.5 coarse sand (Zone III) : 3 graded stone aggregate 20 mm nominal size).	1.9460	cum	10440.0	20316.24	INR Twenty Thousand Three Hundred & Sixteen and Paise Twenty Four Only
6.06	5.9.1 : Centering and shuttering including strutting, etc. and removal of form for Foundations, footings, bases of columns, etc for mass concrete	3.6000	sqm	310.0	1116.00	INR One Thousand One Hundred & Sixteen Only
6.07	5.9.5 : Centering and shuttering including strutting, etc. and removal of form for Lintels, beams, plinth beams, girders, brusses and cantilevers	36.8100	sqm	485.0	17852.85	INR Seventeen Thousand Eight Hundred & Fifty Two and Paise Eighty Five Only
6.08	5.9.6 : Centering and shuttering including strutting, etc. and removal of form for Columns, Pillars, Piers, Abutments, Posts and Struts	13.9200	sqm	660.0	9187.20	INR Nine Thousand One Hundred & Eighty Seven and Paise Twenty Only
6.09	5.22.6 : Steel reinforcement for R.C.C work including straightening, cutting, bending, placing in position and binding all complete upto plinth level Thermo - Mechanically Treated bars of grade Fe-500D or more	898.9400	kilogram	79.0	71016.26	INR Seventy One Thousand & Sixteen and Paise Twenty Six Only
6.1	13.1.1 : 12 mm cement plaster of mix:1:4 (1 cement : 4 fine sand)	65.0260	sqm	340.0	22108.84	INR Twenty Two Thousand One Hundred & Eight and Paise Eighty Four Only
6.11	13.21 : Extra for providing and mixing water proofing material in cement plaster work in proportion recommended by the manufacturers.	13.6000	kg	16.0	217.60	INR Two Hundred & Seventeen and Paise Sixty Only

VEDA
ENGINEERING CONSTRUCTIONS
MULHAKKUNNU, P.O
MUR - 610673

Chief Engineer
~~XXXXXXXXXXXX~~ Structure
Development Corporation Ltd.
Thiruvananthapuram - 695024

6.12	13.43.1 : Applying one coat of water thinnable cement primer of approved brand and manufacture on wall surface. Water thinnable cement primer	65.0260	sqm					52.0	3381.35	INR Three Thousand Three Hundred & Eighty One and Paise Thirty Five Only
6.13	13.44.1 : Finishing walls with water proofing cement paint of required shade. New work (Two or more coats applied @ 3.84 kg/10 sqm)	65.0260	sqm					30.0	1950.78	INR One Thousand Nine Hundred & Fifty and Paise Seventy Eight Only
7	DEMOLISHING SHED									
7.01	15.7.4 : Demolishing brick work manually / by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-Charge. In cement mortar	9.6010	cum					1190.0	11425.19	INR Eleven Thousand Four Hundred & Twenty Five and Paise Nineteen Only
7.02	15.9.2 : Demolishing stone rubble masonry manually / by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-Charge. In cement mortar	8.3210	cum					1425.0	11857.43	INR Eleven Thousand Eight Hundred & Fifty Seven and Paise Forty Two Only
7.03	15.12.1 : Dismantling doors, windows and clerestory windows (steel or wood) shutter including chowkhatas, architrave, holdfasts etc. complete and stacking within 50 metres lead. Of area 3 sq. metres and below	10.0000	each					225.0	2250.00	INR Two Thousand Two Hundred & Fifty Only
7.04	15.15.1 : Extra for dismantling trusses, rafters, purlins etc. of wood work for every additional span of one metre or part thereof beyond 10 metres. Of sectional area 40 square centimetres and above	10.0000	cum per meter span					46.0	460.00	INR Four Hundred & Sixty Only
7.05	15.28.2 : Dismantling roofing including ridges, hips, valleys and gutters etc., and stacking the material within 50 metres lead of Asbestos Sheet	57.6000	sqm					120.0	6912.00	INR Six Thousand Nine Hundred & Twelve Only
8	Plumbing									
8.01	50.18.7.2.2 : Providing and fixing PVC pipes, fittings including fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step PVC solvent cement and testing of joints complete as per direction of Engineer-in-Charge 20 mm dia 10 Kg/cm ² Internal work - Exposed on wall	60.0000	metre					188.0	11280.00	INR Eleven Thousand Two Hundred & Eighty Only

VEDA
ENGINEERING CONSTRUCTIONS
 MUZHAKKUNNU, P.O
 KANNUR - 670673

Shree A.P.
 Director
 Development Corporation Ltd.
 Thiruvananthapuram - 695024

8.02	50.18.7.3.2 : Providing and fixing PVC pipes, fittings including fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step PVC solvent cement and testing of joints complete as per direction of Engineer-in-Charge 25 mm dia 10Kgf/ cm ² - Internal work- Exposed on wall	60.0000	metre				200.0	12000.00	INR Twelve Thousand Only
8.03	50.18.7.4.2 : Providing and fixing PVC, pipes fittings including fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step PVC solvent cement and testing of joints complete as per direction of Engineer-in-Charge 32 mm dia 6 Kg/cm ² - Internal work- Exposed on wall	60.0000	metre				225.0	13500.00	INR Thirteen Thousand Five Hundred Only
8.04	50.18.7.6.2 : Providing and fixing PVC pipes, fittings including fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step PVC solvent cement and testing of joints complete as per direction of Engineer-in-Charge 50 mm dia 6 Kg/cm ² - Internal work- Exposed on wall	40.0000	metre				300.0	12000.00	INR Twelve Thousand Only
8.05	17.34.1 : Providing and fixing toilet paper holder-C.P. Brass	2.0000	no				545.0	1090.00	INR One Thousand & Ninety Only
8.06	51.19.ST4 : Supplying and installing ready made PVC Septic tank including the cost of carriage, trenching, placing at the level below ground level as specified as per the direction of engineer in charge (Provision for CC/RCC/Sand/50mm aggregate for the preparation of bed shall be paid separately) 4. 35 to 50 flush capacity	1.0000	each				43660.0	43660.00	INR Forty Three Thousand Six Hundred & Sixty Only
8.07	19.33 : Constructing soak pit 1.20x1.20 m filled with brickbats including S.W. drain pipe 100 mm diameter and 1.20 m long complete as per standard design.	1.0000	each				3210.0	3210.00	INR Three Thousand Two Hundred & Ten Only
8.08	od188481/2020_2021 : Providing and fixing (UN0002) Universal Angle Cook of superior quality Jaguar or equivalent	2.0000	each				5400.0	10800.00	INR Ten Thousand Eight Hundred Only
8.09	od188482/2020_2021 : Providing and fixing (579 CHR) HEALTH FAUCET of Superior quality Jaguar or equivalent brand	2.0000	each				1930.0	3860.00	INR Three Thousand Eight Hundred & Sixty Only

VEDA
ENGINEERING CONSTRUCTIONS
 MUZHAKKUNNU, P.O
 KANNUR - 670673

Sheeresh

Development Corporation Ltd.
 Thiruvananthapuram - 695024

8.1	odt188483/2020_2021 : Providing and fixing (089 ALD c) stop cock of superior quality 15 mm nominal bore Jaguar or equivalent brand	4.0000	each			1125.0	4500.00	INR Four Thousand Five Hundred Only
8.11	odt188484/2020_2021 : Providing and fixing superior quality brand CP Soap Dish Holder concealed fitting arrangements, weighing not less than 106 gms	2.0000	each			860.0	1720.00	INR One Thousand Seven Hundred & Twenty Only
8.12	odt188485/2020_2021 : Providing and fixing C.P. brass bib cock of superior quality Jaguar or equivalent brand conforming to IS 8931. 15 mm nominal bore	2.0000	each			1715.0	3430.00	INR Three Thousand Four Hundred & Thirty Only
8.13	odt188486/2020_2021 : Providing and fixing superior quality white vitreous china pedestal type water closet (European type) with seat and lid. 10 litre low level white vitreous china flushing cistern & C.P. flush bend with fittings & C.I brackets. 40 mm flush bend, overflow arrangement with specials of standard make and mosquito proof coupling of approved municipal design complete. Including painting of fittings and brackets, cutting and making good the walls and floors wherever required. W.C. pan with ISI marked white solid plastic seat and lid JAQUAR LYS-WHT-38851S300UFSM or Equivalent approved municipal design complete. Including painting of fittings and brackets, cutting and making good the walls and floors wherever required: W.C. pan with ISI marked white solid plastic seat and lid	2.0000	each			26330.0	52660.00	INR Fifty Two Thousand Six Hundred & Sixty Only
8.14	odt188487/2020_2021 : Providing and fixing Cavier SS towel rod complete with brackets fixed to wooden cleats with CP brass screws with concealed fitting arrangement of approved quality and colour. JAQUAR ACN-1111SM or Equivalent	2.0000	each			1500.0	3000.00	INR Three Thousand Only
8.15	odt188488/2020_2021 : Providing and fixing superior quality White Vitreous China Wash basin size 630X450mm with a pair of 15 mm C. P. brass pillar taps with C.I. brackets. 32 mm waste pipe of standard pattern, including painting of fittings and brackets, cutting and making good the walls wherever required ect. complete. JAQUAR ARS-WHT-39803 or Equivalent	2.0000	each			9950.0	19900.00	INR Nineteen Thousand Nine Hundred Only
9	Landscape							

VEDA
ENGINEERING CONSTRUCTIONS
 MUZHAKKUNNU. P.O
 KANNUR - 670673

Infrastructure
Development Corporation Ltd.
 Thiruvananthapuram - 695024

9.01	od92352/2020_2021 : Supplying and planting of approved trees species of a height 2.0m to 2.5m, at the specified location as shown in the drawing. Rate shall include Cost of plants, soil work inclusive of red soil, sand and manure mix staking and planting of trees sapling, replacement of dead trees and for providing a pit size 75 x 75 x 75 cm and maintaining the planting till it is handed over from the date of planting. (1) Plumeria Alba	5.0000	each				2675.0	13375.00	INR Thirteen Thousand Three Hundred & Seventy Five Only
9.02	od92353/2020_2021 : Supplying and planting of approved Hedge Plants at required spacing as shown in drawing. Rate shall include cost of plants soil work, manure and fertilizers used in top dressing, chemical and mechanical pest control, staking and maintaining the planting till it is handed over from the date of planting labour charges, pest control operating etc. (4)Ixora novagrani	20.0000	each				965.0	19300.00	INR Nineteen Thousand Three Hundred Only
9.03	od92354/2020_2021 : Supplying and planting of approved shrubs at required spacing as shown in drawing. Rate shall include cost of plants soil work, manure and fertilizers used in top dressing, chemical and mechanical pest control, staking and maintaining the planting till it is handed over from the date of planting labour charges, pest control operating etc. (13)Tabernaemontana green	20.0000	each				640.0	12800.00	INR Twelve Thousand Eight Hundred Only
9.04	od92355/2020_2021 : Supplying and planting of approved shrubs at required spacing as shown in drawing. Rate shall include cost of plants soil work, manure and fertilizers used in top dressing, chemical and mechanical pest control, staking and maintaining the planting till it is handed over from the date of planting labour charges, pest control operating etc. (9)Oleander tall	10.0000	each				640.0	6400.00	INR Six Thousand Four Hundred Only
9.05	od92356/2020_2021 : Supplying and planting of approved shrubs at required spacing as shown in drawing. Rate shall include cost of plants soil work, manure and fertilizers used in top dressing, chemical and mechanical pest control, staking and maintaining the planting till it is handed over from the date of planting labour charges, pest control operating etc. (7)Gardenia	10.0000	each				860.0	8600.00	INR Eight Thousand Six Hundred Only

Checked

Infrastructure

Development Corporation Ltd.

Thiruvananthapuram - 695024

VEDA
ENGINEERING CONSTRUCTIONS
MUZHAKKUNNU, PO
KANPUR - 670673

9.06	odt188507/2020_2021 : Setting up of a document with Photographs of site before and after the work. The item includes developing of a photographs to a size of 6"x4" and preparing a booklet.	20.0000	each					215.0	4300.00	INR Four Thousand Three Hundred Only
10	Electrical work									
10.01	1.10.3 : Wiring for light point/ fan point/ exhaust fan point/ call bell point with 1.5 sq.mm FRLS PVC insulated copper conductor single core cable in surface / recessed medium class PVC conduit with modular switch, modular plate, suitable GI box and earthing the point with 1.5 sq.mm. FRLS PVC insulated copper conductor single core cable etc as required. Group C	25.0000	point					1070.0	26750.00	INR Twenty Six Thousand Seven Hundred & Fifty Only
10.02	1.55.3 : Wiring for group controlled (looped) light point/fan point/exhaust fan point/ call bell point (without independent switch etc.) with 1.5 sq. mm FRLS PVC insulated copper conductor single core cable in surface/ recessed PVC conduit, and earthing the point with 1.5 sq. mm FRLS PVC insulated copper conductor single core cable etc. as required. Group C	25.0000	point					5400.0	135000.00	INR One Lakh Thirty Five Thousand Only
10.03	1.14.1 : Wiring for circuit/ submain wiring alongwith earth wire with the following sizes of FRLS PVC insulated copper conductor, single core cable in surface / recessed medium class PVC conduit as required 2x1.5 sq.mm + 1X1.5 sq.mm earth wire	98.0000	metre					161.0	15778.00	INR Fifteen Thousand Seven Hundred & Seventy Eight Only
10.04	1.14.2 : Wiring for circuit/ submain wiring alongwith earth wire with the following sizes of FRLS PVC insulated copper conductor, single core cable in surface / recessed medium class PVC conduit as required 2X 2.5 sq. mm + 1 X 2.5 sq. mm earth wire	50.0000	metre					192.0	9600.00	INR Nine Thousand Six Hundred Only
10.05	1.14.3 : Wiring for circuit/ submain wiring alongwith earth wire with the following sizes of FRLS PVC insulated copper conductor, single core cable in surface / recessed medium class PVC conduit as required 2 X 4 sq. mm + 1 X 4 sq. mm earth wire	30.0000	metre					235.0	7050.00	INR Seven Thousand & Fifty Only
10.06	1.17.3 : Supplying and drawing following sizes of FRLS PVC insulated copper conductor, single core cable in the existing surface / recessed steel/ PVC conduit as required. 3 X 1.5 sq.mm	10.0000	metre					75.0	750.00	INR Seven Hundred & Fifty Only

VEDA
ENGINEERING CONSTRUCTIONS
 MUZHAKKUNNU P.O
 KANNUR - 670973

Ch. M. Sreedhar

Kerala Irrigation Infrastructure
 Development Corporation Ltd.
 Thiruvananthapuram - 695024

10.07	1.17.12 : Supplying and drawing following sizes of FRLS PVC insulated copper conductor, single core cable in the existing surface / recessed steel/ PVC conduit as required: 3 x 2.5 sq. mm	40.0000	metre					107.0	4280.00	INR Four Thousand Two Hundred & Eighty Only
10.08	1.31 : Supplying and fixing suitable size GI box with modular plate and cover in front on surface or inrecess, including providing and fixing 3 pin 5/6 amps modular socket outlet and 5/6 amps modular switch, connection etc. as required. (For light plugs to be used in non residential buildings).	2.0000	each					450.0	900.00	INR Nine Hundred Only
10.09	1.32 : Supplying and fixing suitable size GI box with modular plate and cover in front on surface or in recess, including providing and fixing 6 pin 5/6 & 15/16 amps modular socket outlet and 15/16 amps modular switch, connection etc. as required.	1.0000	each					590.0	590.00	INR Five Hundred & Ninety Only
10.1	1.24.1 : Supplying and fixing following modular switch/ socket on the existing modular plate & switch box including connections but excluding modular plate etc. as required: 5/6 amps switch	12.0000	each					118.0	1416.00	INR One Thousand Four Hundred & Sixteen Only
10.11	1.24.3 : Supplying and fixing following modular switch/ socket on the existing modular plate & switch box including connections but excluding modular plate etc. as required: 15/16 amp switch	2.0000	each					160.0	320.00	INR Three Hundred & Twenty Only
10.12	1.24.4 : Supplying and fixing following modular switch/ socket on the existing modular plate & switch box including connections but excluding modular plate etc. as required: 3 pin 5/6 amp socket outlet	11.0000	each					118.0	1298.00	INR One Thousand Two Hundred & Ninety Eight Only
10.13	1.24.5 : Supplying and fixing following modular switch/ socket on the existing modular plate & switch box including connections but excluding modular plate etc. as required: 6 pin 15/16 amp socket outlet	3.0000	each					215.0	645.00	INR Six Hundred & Forty Five Only
10.14	1.27.4 : Supplying and fixing following size/ modules: GI box alongwith modular base & cover plate for modular switches in recess etc as required: 6 Module (200mmX75mm)	5.0000	each					364.0	1820.00	INR One Thousand Eight Hundred & Twenty Only

10.15	90.10.1.3 : Supply & Fixing the following types/ sizes of boxes suitable for modular accessories in surface/ recess including making good the damages, colour washing etc as required (RoHS compliant) 3 module moulded plastic box on surface	3.0000	each					225.0	675.00	INR Six Hundred & Seventy Five Only
10.16	90.10.3.15 : Supply and Fixing the following modular switches & accessories in the existing front plates and giving necessary connections as required (RoHS compliant) 32A DP switch with indicator	1.0000	each					600.0	600.00	INR Six Hundred Only
10.17	od338430/2020_2021 : Supply, conveyance, installation, testing and commissioning of ceiling fans of the following sizes using standard accessories excluding resistance type regulator, wiring the down rod with 16/0.20mm PVC insulated and PVC sheathed 650/1100V grade 3 core round copper conductor flex wire or with extended original wiring etc. as required.
1200mm sweep -5star rated ceiling fan complete with 300mm down rod , canopies, shackles and blades and resistance type regulator working on 230V/240V single phase A/C	5.0000	each					2240.0	11200.00	INR Eleven Thousand Two Hundred Only
10.18	od153713/2020_2021 : Supply, installation , testing and commissioning of exhaust fans of size up to 450mm in the existing opening, fixing necessary anchor bolts / bolt and nuts etc. as required including giving connections with the supplied wire along with the exhaust fan.300/305mm light duty	3.0000	each					2085.0	6255.00	INR Six Thousand Two Hundred & Fifty Five Only
10.19	90.4.9 : Charges for cutting holes suitable for accommodating exhaust fans above 305mm sweep and up to 450mm sweep including plastering colour washing etc. as required.	3.0000	each					545.0	1635.00	INR One Thousand Six Hundred & Thirty Five Only
10.2	90.4.1 : Supply and installation of suitable size MS rod type fan clamp in the RCC slab as per IS 732 as required.	3.0000	each					160.0	480.00	INR Four Hundred & Eighty Only
10.21	90.4.2 : Supply and installation of suitable size MS belt type fan clamp fabricated from flat iron 40 x 6 mm, 150mm long x 2 Nos with M.S. rod bent to shape, neatly painted with 2 coats of enamel paint over a coat of red oxide primer as per IS 732 as required.	2.0000	each					177.0	354.00	INR Three Hundred & Fifty Four Only

VEDA
ENGINEERING CONSTRUCTIONS
 MUZHAKKUNNU, P.O
 KANNUR - 670673

Science
 Director
 Kerala Irrigation Infrastructure
 Development Corporation Ltd.
 Thiruvananthapuram - 695024

10.22	1.25 : Supplying and fixing two module stepped type electronic fan regulator on the existing modular plate switch box including connections but excluding modular plate etc. as required.	5.0000	each					407.0	2035.00	INR Two Thousand & Thirty Five Only
10.23	1.33 : Supplying and fixing 3 pin, 5 amp ceiling rose on the existing junction box/ wooden block including connection etc as required.	22.0000	each					64.0	1408.00	INR One Thousand Four Hundred & Eight Only
10.24	od161033/2020_2021 : SITC of Decorative, wall mounting fixture, in durable plastic body & amp; designer mesh in gold finish suitable for 9 W LED lamp. (Havells Glaze or equivalent)	13.0000	each					803.0	10439.00	INR Ten Thousand Four Hundred & Thirty Nine Only
10.25	90.3.19.3 : Supply conveyance, installation, testing and commissioning the light fittings of following types made from CRCA sheet 0.5mm thickness with all accessories and lamps directly on wall and giving connections with 16/0.20 mm 3 core PVC insulated and sheathed round copper conductor flex wire or extending the original wiring and giving connections as required 1200 mm 1X20W LED Lamp with box type fixture	4.0000	each					1250.0	5000.00	INR Five Thousand Only
10.26	od153715/2020_2021 : Supply and fixing compact and aesthetic SBK finish outdoor 8W LED uplight and giving connection as required (Seron SRL 1005 or equivalent)	9.0000	each					1250.0	11250.00	INR Eleven Thousand Two Hundred & Fifty Only
10.27	od153716/2020_2021 : SITC of Garden spike lights, Integrated COB 12W LED, 12.2 & times; 8.5 & times; 8.5 cm, aluminum material. (Philips Garden Spike or equivalent)	4.0000	each					1926.0	7704.00	INR Seven Thousand Seven Hundred & Four Only
10.28	od153717/2020_2021 : SITC of 12W LED hanging light with extruded aluminum housing with microtexture powder coating. (Mipro Halo Plus -LD99-151-XXX57PMMH or equivalent).	14.0000	each					3030.0	42420.00	INR Forty Two Thousand Four Hundred & Twenty Only
10.29	od160722/2020_2021 : Supply and providing foundation bolts of size 20mm dia, 50cm long including nuts and washers for lamp poles, bollards, outdoor lamp fittings etc.	34.0000	kilogram					86.0	2924.00	INR Two Thousand Nine Hundred & Twenty Four Only

Devaraj

Chief Engineer

Kerala Irrigation Infrastructure
Development Corporation Ltd.
Thiruvananthapuram - 695024

VEDA
ENGINEERING CONSTRUCTIONS
MUZHAKKUNNU, PO
KANNUR - 670673

10.3	od160889/2020_2021 : Supply and fixing cast iron post top lantern 28W inbuilt LED conforming to IP65 with shade of size 540x450mm with powder coated finish an giving connection as required.	2.0000	each			14500.0	29000.00	INR Twenty Nine Thousand Only
10.31	od160890/2020_2021 : Supplying & fixing Cast iron lamp pole of height 4mtrs. base dia:250mm and top dia.75mm (weight 110kg. Arox. with provision for fixing MCB and cably entry/exit at bottom made of FG15 grade cast iron with MRF epoxy black finish over a coat of zinc chromate base on existing concrete foundation using foundation bolts, nuts and washers.	2.0000	each			22400.0	44800.00	INR Forty Four Thousand Eight Hundred Only
10.32	od160723/2020_2021 : SITC of New generation, energy saving, environmental friendly, long life aesthetically designed aluminium bollard landscape luminaire for diffused lighting with high power LED as light source. 8W, 1m height, IP 65. (Havelis BAMBOOBL8WLED757PSYMTOPCM or equivalent)	8.0000	each			4310.0	34480.00	INR Thirty Four Thousand Four Hundred & Eighty Only
10.33	od160724/2020_2021 : Supply of 2.5sqmm 3core PVC/XLPE insulated armoured copper conductor cable for working voltage upto and including 1100V conforming to IS1584/Part I/1988 for PVC & IS7098 PartI for XLPE	100.0000	metre			155.0	15500.00	INR Fifteen Thousand Five Hundred Only
10.34	90.11.1.14 : Supply and installation of sheet steel, phosphatised and painted, dust and vermin proof enclosure of MCB DB including copper /brass bus bar, neutral link, earth bus and DIN rail suitable for fixing MCB/ Isolator etc. fixed on wall using suitable anchor bolts or fixed in recess including cutting hole on the wall, making good the damages, colour washing etc. as required4 way (8+12) - double cover TPN vertical DB with provision for fixing 4P MCB / Isolator/ RCCB/ RCBO as incomer and SP/ TP MCB as outgoing (IP 42/43)	1.0000	each			6900.0	6900.00	INR Six Thousand Nine Hundred Only
10.35	90.11.1.10 : Supply and installation of sheet steel, phosphatised and painted, dust and vermin proof enclosure of MCB DB including copper /brass bus bar, neutral link, earth bus and DIN rail suitable for fixing MCB/ Isolator etc. fixed on wall using suitable anchor bolts or fixed in recess including cutting hole on the wall, making good the damages, colour washing etc. as required4 way (8+12) - three phase double cover (IP 42/43)	1.0000	each			2940.0	2940.00	INR Two Thousand Nine Hundred & Forty Only

VEDA ENGINEERING CONSTRUCTIONS
 KOLZHAKKUNNU, P.O
 KANNUR - 670633

Chief Engineer Infrastructure
 Development Corporation Ltd.
 Thiruvananthapuram - 695024

10.36	2.15.2 : Supplying and fixing following rating, four pole, (three phase and neutral), 415 volts, residual current circuit breaker (RCCB), having a sensitivity current upto 300 milliamperes in the existing MCB DB complete with connections, testing and commissioning etc. as required.40 amps	1.0000	each				3000.0	3000.00	INR Three Thousand Only
10.37	2.14.1 : Supplying and fixing following rating, double pole, (single phase and neutral), 240 volts, residual current circuit breaker (RCCB), having a sensitivity current upto 300 milliamperes in the existing MCB DB complete with connections, testing and commissioning etc. as required.25 amps	3.0000	each				2325.0	6975.00	INR Six Thousand Nine Hundred & Seventy Five Only
10.38	od153725/2020_2021 : Supply and fixing following rating, 4pole, 415V RCBO in the existing MCB DB and giving connection as required. 63A, 30mA	1.0000	each				600.0	600.00	INR Six Hundred Only
10.39	od153726/2020_2021 : Supply and fixing following rating, 4pole, 415V RCBO in the existing MCB DB and giving connection as required. 32A, 30mA	1.0000	each				4515.0	4515.00	INR Four Thousand Five Hundred & Fifteen Only
10.4	2.10.5 : Supplying and fixing 5 amps to 32 amps rating, 240/415 volts, "C" curve, miniature circuit breaker suitable for inductive load of following poles in the existing MCB DB complete with connections, testing and commissioning etc. as required. Triple pole and neutral	1.0000	each				1250.0	1250.00	INR One Thousand Two Hundred & Fifty Only
10.41	2.3.1 : Supplying and fixing following way, single pole and neutral, sheet steel, MCB distribution board, 240 V, on surface/ recess, complete with tinned copper bus bar, neutral bus bar, earth bar, din bar, interconnections, powder painted including earthing etc. as required. (But without MCB/RCCB/isolator)6 way, Double door	3.0000	each				1330.0	3990.00	INR Three Thousand Nine Hundred & Ninety Only
10.42	2.10.1 : Supplying and fixing 5 amps to 32 amps rating, 240/415 volts, "C" curve, miniature circuit breaker suitable for inductive load of following poles in the existing MCB DB complete with connections, testing and commissioning etc. as required. Single pole	14.0000	each				245.0	3430.00	INR Three Thousand Four Hundred & Thirty Only

Research

Chief Engineer

Kerala Irrigation Infrastructure
Development Corporation Ltd.

Thiruvananthapuram - 695024

VEDA
ENGINEERING CONSTRUCTION'S
MUZHAKKUNNU, P.O
KANNUR - 670673

10.43	2.10.3 : Supplying and fixing 5 amps to 32 amps rating, 240/415 volts, "C" curve, miniature circuit breaker suitable for inductive load of following poles in the existing MCB DB complete with connections, testing and commissioning etc. as required Double pole	3.0000	each	655.0	1965.00	INR One Thousand Nine Hundred & Sixty Five Only
10.44	2.10.4 : Supplying and fixing 5 amps to 32 amps rating, 240/415 volts, "C" curve, miniature circuit breaker suitable for inductive load of following poles in the existing MCB DB complete with connections, testing and commissioning etc. as required Triple pole	1.0000	each	990.0	990.00	INR Nine Hundred & Ninety Only
10.45	od153735/2020_2021 : Supply & installation of dust and vermin proof, 3 Phase Synlex Meter Board GS-MB-6535(size 760x450x260x) and to fix KSEB meters, fuse units, CT etc as required including fixing it on wall, making good the damages colour washing etc. as required.	1.0000	each	5160.0	5160.00	INR Five Thousand One Hundred & Sixty Only
10.46	2.1.2 : Providing and fixing following capacity TP&N disconnecter fuse switch unit inside the existing panel board with ISI marked HRC fuses including drilling holes in cubicle panel, making connections, etc. as required.63 Amp TP & N	1.0000	each	2980.0	2980.00	INR Two Thousand Nine Hundred & Eighty Only
10.47	od153740/2020_2021 : Supply and fixing 63 A, 415 V, 2 way neutral link mounted on DMC/ SMC base in the existing meter board.	1.0000	each	188.0	188.00	INR One Hundred & Eighty Eight Only
10.48	od153741/2020_2021 : Supply and fixing 63A HRC fuse base with fuse link in the existing meter board.	3.0000	each	182.0	546.00	INR Five Hundred & Forty Six Only
10.49	1.21.2 : Supplying and fixing of following sizes of medium class PVC conduit along with accessories in surface/ recess including cutting the wall and making good the same in case of recessed conduit as required.25 mm	2.0000	metre	96.0	192.00	INR One Hundred & Ninety Two Only
10.5	5.4 : Earthing with G.I. earth plate 600 mm X 600 mm X 6 mm thick including accessories, andproviding masonry enclosure with cover plate having locking arrangement and watering pipe of 2.7 metre long etc. with charcoal/ coke and salt as required.	2.0000	set	6110.0	12220.00	INR Twelve Thousand Two Hundred & Twenty Only


VEDA
ENGINEERING CONSTRUCTIONS
 MUZHAKKUNNU, P.O.
 ANNUR - 670673


 Kerala Irrigation Infrastructure
 Development Corporation Ltd.
 Thiruvananthapuram - 695024

10.51	5.13 : Providing and laying earth connection from earth electrode with 4.00 mm dia copper wire in 15mm dia G.I. pipe from earth electrode including connection with copper thimble excavation and re-filling as required.	30.0000	metre					257.0	7710.00	INR Seven Thousand Seven Hundred & Ten Only
10.52	5.14 : Providing and fixing 25 mm X 5 mm copper strip on surface or in recess for connections etc. as required.	0.3000	metre					985.0	295.50	INR Two Hundred & Ninety Five and Paise Fifty Only
10.53	5.17 : Providing and fixing 4.00 mm dia copper wire on surface or in recess for loop earthing as required.	50.0000	metre					123.0	6150.00	INR Six Thousand One Hundred & Fifty Only
10.54	90.12.1.3 : Supply & laying of one number PVC insulated and PVC sheathed armoured aluminium power cable of 1.1KV grade of the following sizes in ground including excavation of trench of size 35 x 75 cm, refilling the trench etc. as required but excluding sand cushioning and protective covering (in ordinary soil). 2 core 10 sq mm	145.0000	metre					375.0	54375.00	INR Fifty Four Thousand Three Hundred & Seventy Five Only
10.55	90.12.7.3 : Supply, laying and clamping of 1 no. PVC insulated and PVC sheathed armoured aluminium power cable, 1.1 KV grade of the following sizes using clamps noted along with the cables, spacing of clamps not exceeding 60cms, making good the damages, colour washing etc. as required. 2 core 10 sq mm with factory made clamp	100.0000	metre					220.0	22000.00	INR Twenty Two Thousand Only
10.56	90.12.7.40 : Supply, laying and clamping of 1 no. PVC insulated and PVC sheathed armoured aluminium power cable, 1.1 KV grade of the following sizes using clamps noted along with the cables, spacing of clamps not exceeding 60cms, making good the damages, colour washing etc. as required. 4 core 10 sq mm with factory made clamp	10.0000	metre					240.0	2400.00	INR Two Thousand Four Hundred Only
10.57	90.12.7.42 : Supply, laying and clamping of 1 no. PVC insulated and PVC sheathed armoured aluminium power cable, 1.1 KV grade of the following sizes using clamps noted along with the cables, spacing of clamps not exceeding 60cms, making good the damages, colour washing etc. as required. 4 core 25 sq mm with factory made clamp	10.0000	metre					333.0	3330.00	INR Three Thousand Three Hundred & Thirty Only

Seenick


Chief Engineer

Kerala Irrigation Infrastructure
Development Corporation Ltd.
Thiruvananthapuram - 695024

VERA
ENGINEERING CONSTRUCTIONS
MUZHAKKUNNU P.O
KANNUR - 670673

10.58	9.1.2 : Supplying and making end termination with brass compression gland and aluminium lugs for following size of PVC insulated and PVC sheathed / XLPE aluminium conductor cable of 1.1 KV grade as required. 2 X 10 sq. mm (19mm)	4.0000	set	225.0	900.00	INR Nine Hundred Only
10.59	9.1.32 : Supplying and making end termination with brass compression gland and aluminium lugs for following size of PVC insulated and PVC sheathed / XLPE aluminium conductor cable of 1.1 KV grade as required. 4 X 10 sq. mm (25mm)	2.0000	set	290.0	580.00	INR Five Hundred & Eighty Only
10.6	9.1.34 : Supplying and making end termination with brass compression gland and aluminium lugs for following size of PVC insulated and PVC sheathed / XLPE aluminium conductor cable of 1.1 KV grade as required. 4 X 25 sq. mm (28mm)	2.0000	set	365.0	730.00	INR Seven Hundred & Thirty Only
10.61	9.16.1.3 : Supply and drawing bare earthing conductors of the following sizes along with wiring/ cables and giving connection as required. 3.15 mm copper conductor (10 SWG)	300.0000	metre	60.0	18000.00	INR Eighteen Thousand Only
10.62	9.0.12.9.2 : Supplying, laying and jointing of the following sizes of double wall corrugated (DWC) pipes made out of HDPE conforming to IS 14930 Part II for mechanical protection to underground power cables with all required accessories in ground in the existing trench 50/38 mm or nearest size	150.0000	metre	152.0	22800.00	INR Twenty Two Thousand Eight Hundred Only
Total in Figures				6279215.13		INR Sixty Two Lakh Seventy Nine Thousand
Quoted Rate in Words		INR Sixty Two Lakh Seventy Nine Thousand Two Hundred and Two Hundred and Paise Thirteen Only				


VEDA
ENGINEERING CONSTRUCTIONS
 MUZHAKKUNNU, P.O
 KANNUR - 670673


Chief Engineer
 Kerala Irrigation Infrastructure
 Development Corporation Ltd.
 Thiruvananthapuram - 695024